



Project Development





Kick-Off | October 10, 2023

Agenda


- Project Background
- Schedule
- Existing Conditions & City Objectives
- Next Steps







Project Background: Project Boundary







Kick-Off | October 10, 2023

Project Background: 5 W's

Who:

- Broward MPO
- Kimley-Horn
- City of Fort Lauderdale
- Broward County
- FDOT

What:

- Approve a Locally Preferred Concept (15% Design)
- Complete Streets elements
- MTECC Bid Package

Where:

17th Street from SW 9 Av to US1

Why:

- TIP (FTA capital funds = \$6.8 million)
- Previous BMPO Studies: Complete Streets Master Plan; Walking Audit
- Previous City Studies: LauderTrail; Connecting the Blocks; Preliminary Lane Elimination Assessment
- Broward Commuter Rail


When:

- LPC must be approved by City Commission by April 2024
- Design in 2024 / 2025
- Construction in 2026/2027






Project Schedule



Segment 1: SW 9 Av to west end of SW 4 Av







Sidewalk end; South ROW





Existing Conditions:

- Sidewalk Gaps (south ROW)
- Missing sidewalk extensions at intersections
- Sloped sidewalks near SW 4 Av
- No bicycle facilities
- No marked crosswalks at SW 8 Av and SW 6 Av
- No ped-scale lighting
- Minimal Street lighting
- 4-way 3-way Stops intersections
- SW 8 Av is off-set intersection
- No traffic calming features
- School zone pavement markings

- ✓ Fill in missing sidewalk gaps
- Fill in missing sidewalk extensions at intersections
- ✓ Sharrows / "Share the Road" signage
- ✓ Mark all crosswalks
- Traffic calming features both along roadway and at intersections
- ✓ Improve roadway lighting
- ✓ Improve stormwater management
- Improve safety of intersection at SW 9 Av (N/S traffic)
- Realign pavement markings just west of SW 4 Av

Segment 2: SW 4 Av to west of Andrews Av

5



Faded crosswalks @ SW 4 Av



Bus Stop @ SW 4 Av, SE corner



Crossing @ SW 3 Av median break



No crosswalk @ SW 2 Av, south ROW





Existing Conditions:

- @ SW 4 Av: Faded crosswalk markings; Ped's cross 5 lanes; Permissive only LTs; 1 streetlight (in east median); school crossing guards; school bus stops
- West of FEC: Shade trees in north and south ROW; school speed zone
- Missing sidewalk over FEC
- No bicycle facilities
- No marked crosswalks over side streets
- Missing curb extensions and accessible components
- No ped-scale lighting; Minimal Street lighting
- Pedestrians crossing not at marked crosswalks
- Flooding in south ROW between SW 2 Av SW 3 Av
- SW 17 St @ SW 1 Av is on BMPO High Injury Network (2017 – 2021 crashes)

- Raised, separated, protected bike facility (reduce outside lane width or narrow median)
- ✓ Marked crosswalks over side streets
- ✓ High emphasis crosswalk markings
- ✓ ADA compliant facilities
- ✓ Improved street lighting
- ✓ Ped-Scale Lighting
- ✓ Relocate FPL poles from medians
- ✓ Mid-block crosswalk near SW 3 Av
- ✓ Protect trees
- ✓ Convert SW 4 Av signal to Mast Arm; Assess need for LT phase
- ✓ Improve stormwater management



Segment 3: Andrews Av to SE 3 Av






West view to Andrews Av, Heavy Trucks on Andrews Av



LT Bike activity at Andrews Av









Crossing at SE 1 Av



Riding EB in south shoulder









Existing Conditions:

- @ Andrews Av: Faded crosswalk markings; Permissive only LTs from 17 St; Ped's crossing 6 lanes
- @ SE 3 Av: High visibility crosswalk markings; Ped-Bridge from parking garage to hospital (no street access); Permissive LT on all directions
- No bicycle facilities; bicyclists observed riding in right shoulders
- No marked crosswalks over SE 1 Av or driveways
- Missing curb extensions and accessible components
- Heavy truck traffic on Andrews Av
- No ped-scale lighting
- Use crosswalk sign under ped-bridge
- Ped's observed crossing @ SE 1 Av from hospital employee parking lot to employee entrance
- BCT Stops missing shelters & other amenities
- > SW 17 St @ Andrews Av is on BMPO High


- Raised, separated, protected bike facility
- ✓ Remove "3rd" lane / continuous rightturn lane
- ✓ Keep left turn lanes
- ✓ Tighten median opening and curb radii at SE 1 Av
- ✓ Marked crosswalks over side streets
- ✓ High emphasis crosswalk markings
- ✓ ADA compliant facilities
- ✓ *Improved street lighting* (including under pedestrian bridge)
- ✓ Ped-Scale Lighting
- Assess need for mid-block crossing for hospital parking
- ✓ Increase shading
- Convert both intersection equipment to Mast Arm and other signal improvements
- ✓ Assess need for LT phase
- Improve stormwater management

Segment 4: East of SE 3 Av to west ROW US1





North ROW, west view







Crossing near 500 block

Heavy truck



BCT Stop on south ROW



SW corner, east view



Existing Conditions:

- No bicycle facilities; bicyclists observed riding in right shoulders, darting into roadway, and riding on sidewalk
- North sidewalk at SE 4 Av: connects via landscaped median
- South sidewalk at SE 4 Av: no connection to landscape median (well-worn path visible)
- East of SE 1 Av, south sidewalk abuts back-out \geq parking & is at curb.
- > 20 MPH speed limit at roadway curve
- Heavy Truck traffic on 17 St
- No marked crosswalks over driveways
- Missing curb extensions and accessible components
- No ped-scale lighting
- Ped's observed crossing not at marked crosswalks
- BCT Stops have shelters / amenities
- Stop at SW corner of US1 has sign only

- ✓ Shared Use Path or marked bike facility
- ✓ Remove "3rd" lane / continuous right-turn lane
- Keep left turn lanes \checkmark
- Median or other physical barrier to restrict SB to EB left turns from Whole Foods parking garage
- Enhance landscaping in the \checkmark southern porkchop at SE 4 Av
- Marked crosswalks over side streets
- ✓ ADA compliant facilities
- Ped-Scale Lighting





Project Development





Kick-Off | October 10, 2023